

RAW WATER PUMP STATION

LOCATION:	Innisfail
PRINCIPAL:	<u>Johnstone Shire Council</u> (now Cassowary Coast Regional Council)
REFERENCE:	Mr. Steve Verity (Principal) Phone: 4030 2222 Mr. Geoff Simmers (Superintendent's Engineer & administration) Phone: 4938 4964 October 2000 to August 2001
PERIOD:	
VALUE OF WORKS:	<i>\$1,401,923.60</i>
MAJOR SUBCONTRACTORS:	King Concreting, JM Switchboards, Steve Hibberd Excavator Hire, C & B Consultants, Hornbulk Crane Hire, Win Concrete Pumping
MAJOR SUPPLIERS:	One Steel, CSR Readymix, Tyco, Flygt, Innisfail Quarry, Coates Hire



DETAILS: The works involve the construction of a 12m deep pump well adjoining the Johnstone River, with works to 4m below river level. The pump well is 6.2m diameter and has provision for 2 large 170Kw Flygt pumps.

600/300/250 diameter Ductile Iron cement lined pipe work is used throughout.

Two valve pits, a control building, switchboards and variable speed drives, and telemetry were involved in the project.

Many steelworks items were fabricated in our factory for the project.

Procurement System: Traditional (Lump Sum)

Service Category: New Construction Work

Project Type: Civil Works - foundation

Service Activities: Bulk earthworks, Concreting, Formwork, High level drainage, Engineering Fabrication & Boilermaking, Electrical - specialised, Metal Fabrication, Piped Service Works, Scaffolding, High level Telecommunication Cabling, Water Supply - High.

Project Environment: Sensitive

